EJM BUILDING SOLUTION
TIN: 127 229 260
VRN: 40315266U
Dar Es Salaam,Tanzania
(+255) 754 777 447
(+255) 782 177 120
info@ejm.co.tz
emaremangasy@gmail.com

DATE:13th March , 2026

PROPOSED LGT LOGISTICS OFFICE PARTITION WORKS

10mm TOUGHENED GLASS

VENDOR: EJM BUILDING SOLUTION

CLIENT: LGT LOGISTICS

S/No	ITEM	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
		MAIN WORKS				
1	Glass Partition	10mm thick clear toughened Glass partition framed to Aluminium chanels	70	M2	300,000	21,000,000
2	Drywall Partition	9mm Gypsum boards fixed to Aluminium outer frame on bottom and metal channels on both sides with sound insulation materials finished with paints	48	M2	120,000	5,760,000
3	Frameless Glass door	Frameless tempered glass door with all accessories	6	No	1,000,000	6,000,000
4	Aluminum Door	Aluminum with glass door for store area	1	No	450,000	450,000
5	Sliding door	Aluminum with glass sliding door	1	No	1,200,000	1,200,000
6	Carpet tiles	Office carpet tiles	30	M2	95,000	2,850,000
7	Vinly flooring	Wooden vinly flooring	88	M2	65,000	5,720,000
8	Zebra blinds	Office zebra blinds	29	M2	90,000	2,610,000
9	Pendant light	Linear décor pendant light	5	No	350,000	1,750,000
10	Circular pendant	Circular décor pendant light	1	No	450,000	450,000
11	Bowl light	Reception décor bown light	2	No	150,000	300,000
12	3d design	Remodeling of plan	1	No	300,000	300,000
					TOTAL AMOUNT	**48,390,000.00**